



HDX-63C-NOV

Dakota Digital HDX Instrument Installation For 1963-'65 Chevy Nova 1962 Nova with use of 1963-'65 bezel




Installation

1. First, remove the stock gauge cluster from the dash. Next, remove the four screws holding the metal gauge housing to the bezel.




2. Fit the HDX system to the gauge bezel; make sure to slide the topside of the bezel to the inside of the lip on the HDX system. If the bezel is not fully seated, you will see a gap between the lens and bezel when viewing the gauges from the front. When properly seated, the lens and bezel will fit together tightly with no gaps.




3. Secure the HDX system to the bare bezel using a set of screws provided. Use the smaller 6-20x1.75" for a stock bezel or the larger 8-18x1.75" for a reproduction bezel.



4. Connect the provided Main Harness and the Buzzer (optional for audio feedback) to the back of the HDX system.



5. Re-install the cluster into the vehicle using the factory hardware and refer to the main manual for wiring instructions to complete the HDX installation.



AWARNING: This product can expose you to chemicals including lead, which is known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov



4510 W. 61st St. North Sioux Falls, SD 57107 www.dakotadigital.com dakotasupport@dakotadi

Phone (605) 332-6513 Fax (605) 339-4106

dakotasupport@dakotadigital.com Copyright 2011 - Dakota Digital, Inc.